



**NOTES:**

1. ADHERED WALLS: INSTALL MEMBRANE IN IB VERTIBOND ADHESIVE ADDING NOMINAL RATE OF 1 GAL. PER 60 SQ. FT. NET INSTALLED COVERAGE (50% TO SUBSTRATE ALLOW TO DRY WITH REMAINING 50% TO BACK OF SHEET, INSTALL WHILE TACKY)
2. SECURE FLASHINGS AND METAL WORK IN ACCORDANCE WITH IB SPECIFICATIONS AND FLASHING SECUREMENT TABLE.
3. REFER TO FT AND/OR PT DETAILS FOR APPROVED FLASHING AND PARAPET WALL TERMINATIONS

**APPROVED SUBSTRATE / SEPARATION:**

**NEW CONSTRUCTION - FULLY ADHERED**

- 1/2" PLYWOOD, 7/16" OSB, POURED / PRECAST CONCRETE, OR CEMENT BLOCK / MASONRY WALLS.

**FULLY ADHERED RECOVER OVER APPROVED EXISTING WALL AND BASE FLASHINGS**

- FULL SEPARATION REQUIRED WITH MINIMUM 1/2" PLYWOOD, 1/4" APPROVED GYPSUM COVER BOARD, OR 7/16" OSB.

Scale:

NTS

Detail Name:

**Adhered Tall Wall**

Detail Number:

**WD - 02**

Submitted By:

Address:

Telephone:

Project:

Address: